

**Claymont Schools**  
**201 North Third Street**  
**Dennison, OH 44621**

**BID PACKAGE ATTACHMENTS / REQUIRED WITH BID**

1. \_\_\_\_\_ Workers' Compensation Certificate - Ohio
2. \_\_\_\_\_ Liability Insurance Certificate Copies include Auto and Umbrella Cert.  
\$1,000,000
3. \_\_\_\_\_ Bonding Company Name - Attached to #2
4. \_\_\_\_\_ Affirm of Bidder's Profile / Certification of Signature
5. \_\_\_\_\_ Customer Contacts & Supplier Contacts
6. \_\_\_\_\_ List of all Subcontractor's names, contacts and phone numbers.
7. \_\_\_\_\_ **Contractor to provide all of the above with Sealed Bid.**

Claymont Middle School  
215 E. Sixth St.  
Uhrichsville, Ohio 44683

April 10, 2018

## Addition of Air Conditioning for Claymont Middle School Gymnasium

1. Furnish and install two DX cooling coils for the existing air handlers in the gymnasium.
2. Furnish and install two 20 ton condensing units.
3. Reconnect all duct work
4. Run all refrigerant piping from coils to condensing units.
5. Run condensation drain line from air handlers to approved drain.
6. Install low voltage lines from air handlers to condensing units to thermostats.
7. Install three phase electric from main panel in the gym to the condensing units.
8. Install stand-alone cooling controls.
9. Provide rigging
10. Provide start-up
11. Verify proper operation and training.

Location of condensing units can be placed on lower roof of gym or outside the gym in parking lot.

Work must be completed by August 1<sup>st</sup>, 2018.

Contact Beth Lint for more details or questions.

740-922-5478 ext 12016

[blint@claymontschools.org](mailto:blint@claymontschools.org)